Spring 2022 Link (by link type) (by direction)	Length d	Lanes (new)	Capacity (new)		Update or Addition	Link Cost	Node Cost	Penalty	Maint & Rehab	Cost
Units	(miles)		(vph)			$k	$k	$k	$k	$k
1. Freeway:	60.00	Speed (min/mile) =								
sub-total										
2. Primary Arterial:	60.00	Speed (min/mile) =								
sub-total										
3. Major Arterial:	45.00	Speed (min/mile) =								
sub-total										
4. Minor Arterial:	45.00	Speed (min/mile) =								
8 to 205 CHANGE	0.50	2	900	U	Minor to Major Art	100.00	100.00	1.00	0.00	200.00
150 to 7	0.50	2	900	U	Minor to Major Art	100.00	100.00	1.10	0.00	220.00
sub-total						200.00	200.00			420.00
5. Collector Street:	30.00	Speed (min/mile) =								
205 to 210 Mias	0.50	2	900	U	Collect to Major Art.	100.00	100.00	1.00	0.00	200.00
210 to 220 Mias	1.00	2	900	U	Collect to Major Art.	200.00	100.00	1.00	0.00	300.00
Unchanged Collectors	2.50	1	600	M	Maint on Collectors	50.00				50.00
sub-total						350.00	200.00			550.00
6. Local Street:	15.00	Speed (min/mile) =								
220 to 230 Mias	1.00	2	900	U	Local to Major Art.	200.00	100.00	1.00		300.00
230 to 240 Mias	1.00	2	900	N	New Major + bridge	225.00	100.00	1.20	2x	780.00
240 to 140 4th	1.00	2	900	U	Local to Major Art.	200.00	100.00	1.20		360.00
140 to 150 CH	1.00	2	900	U	Local to Major Art.	200.00	100.00	1.10		330.00
110 to 120	1.00	1	600	U	Local to Collector	50.00	50.00	1.10		110.00
320 to 220 2nd	1.00	1	300	N	New Local	50.00	25.00	1.00		75.00
340 to 240 4th	1.00	1	300	N	New Local	50.00	25.00	1.00		75.00
340 to 345 Mtn	0.50	1	300	N	New Local	25.00	12.50	1.00		37.50
Unchanged Locals	7.00	1	300	M	Maint on Locals	70.00				70.00
sub-total						1070.00	512.50			2137.50
7. Other Links:		Speed (min/mile) =								
sub-total										
8. Ramps:	30.00	Speed (min/mile) =								
sub-total										
9. Centroid Connector	25.00	Speed (min/mile) =								
sub-total										
Grand Total:	19.50					1620.00	912.50			3107.50
Notes:										